NOTES:

1. PORTLAND CEMENT CONCRETE (P.C.C.) SHALL BE 4000 PSI MIN. COMPRESSIVE STRENGTH AT 28 DAYS. ALL CEMENT CONCRETE SHALL HAVE A COARSE AGGREGATE GRADATION CONFORMING TO SIZE No. 67. POLYPROPYLENE OR CELLULOSE FIBERS SHALL BE ADDED TO THE P.C.C. AT 1.5 LBS PER CUBIC YARD. MIX DESIGN SHALL CONFORM TO THE REQUIREMENTS OF SECTION 337.10 OF SSPWC. ALL MATERIALS SHALL CONFORM TO SSPWC.

2. AGGREGATE BASE MATERIAL UNDER SIDEWALKS SHALL BE TYPE 2, CLASS B CRUSHED AGGREGATE BASE. MATERIALS SHALL CONFORM TO SSPWC SECTION 200.

3. SIDEWALK WIDTH "W" SHALL BE PER PLAN.

4. WEAKENED PLANE JOINTS TYPICALLY SHALL BE CONSTRUCTED AT 5 FT INTERVALS OR ACCORDANCE WITH SECTION 312 OF THE SSPWC.

△5. ALL ADJACENT CONCRETE REMOVAL SHALL BE TO NEAT SAW CUT LINES AT RIGHT ANGLES TO NEW SIDEWALK AT NEAREST WEAKENED PLANE JOINT. NO OVERCUTS. DOWEL INTO EXISTING ADJACENT CONCRETE SIDEWALK WITH A MINIMUM OF TWO (2) No. 4 REINFORCEMENT BARS 10" IN LENGTH. DOWELS SHALL BE EQUALLY SPACED ACROSS WIDTH "W" AND DOWELS SHALL PENETRATE A MINIMUM OF 4" INTO EXISTING CONCRETE.

6. SIDEWALKS SHALL NOT BE POURED MONOLITHICALLY WITH CURBS.

7. COLORED CONCRETE AND PAVERS ARE NOT ALLOWED.

8. TUNNELING AND/OR BORING IS NOT ALLOWED.

	STANDARD DETAILS FOR PUBLIC WORKS CONSTRUCTION	DRAWING No.
RENO	NOTES - SIDEWALK DETAIL	R-104B
		APPROVED BY: KK | DATE: 2/2026