NOTES:

1. SIGN MATERIALS, CONSTRUCTION AND PLACEMENT SHALL BE IN CONFORMANCE WITH THE LATEST EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

2. CONCRETE BASE SHALL BE LOCATED AT BACK OF SIDEWALK, UNLESS OTHERWISE DIRECTED BY THE CITY ENGINEER.

3. ALL SIGNS SHALL BE 3M DIAMOND GRADE (DG3), SERIES 4000, SHEETING WITH A CLEAR, TRANSPARENT OVERLAY 3M #1160i (LATEST EDITION) OR APPROVED EQUAL. SHALL BE A MATCHED COMPONENT SYSTEM.

4. OVERLAY ACRYLIC EC FILMS, INKS AND DIGITAL IMAGING USED FOR ASSEMBLY SHALL BE APPROVED FOR USE BY THE MANUFACTURER OF THE SHEETING MATERIAL. THE SERVICE LIFE OF INKS AND FILMS SHALL BE COMPARABLE TO THE SHEETING USED. ALL LETTERS, NUMERALS, SYMBOLS, BORDERS, AND ACCESSORIES AS NECESSARY FOR THE SIGN LEGEND SHALL BE DIRECTLY APPLIED, DIGITALLY PRINTED, OR MOLDED TO FORM AN INTEGRAL SIGN LEGEND AND BACKGROUND ON ALL SIGNS.

5. 2 FEET MINIMUM FROM EDGE OF SIGN TO FACE OF CURB.

6. 6 FEET MINIMUM FROM EDGE OF SIGN TO EDGE OF PAVEMENT WHERE CURB DOES NOT EXIST.

7. SIGN MOUNTING HEIGHT SHALL BE 7 FEET FROM FINISHED GRADE OR ADJACENT ROADWAY PAVEMENT IF NOT BEHIND CURB.

8. FOUNDATION SHALL BE 4000 PSI CONCRETE.

	STANDARD DETAILS FOR PUBLIC WORKS CONSTRUCTION	DRAWING No.
RENO	NOTES - TRAFFIC SIGN INSTALLATION	R-415B
		APPROVED BY: KK / DATE: 2/2026